Handling of Coupled Functional Units

Additional information for User Manual AMTNoT131-02.

Handling procedure during transport

- By forklift truck.

- By 2 slings of 1,000 kg each.

Unpacking the switchboard

- Bring the switchboard still packed as near as possible to its installation location.
- Remove the protective cover.

- Remove the door panels.
- Unscrew the lag-bolts fixing the switchboard to the pallet (4 points in the extremities of the Functional Units).



- Fit the door panels back in place.

Handling of Coupled Functional Units

Installing the switchboard

- Check the evenness of the floor where the switchboard will be installed.
- Lift the switchboard with the slings and place it down slowly, without jerks, in its definitive location.

DO NOT MOVE THE SWITCHBOARD BY SLIDING IT ON THE FLOOR.

Checks

- Wedge the switchboard in place if necessary.
- Ensure that the Functional Units making up the switchboard are joined together and aligned.

Commissioning the switchboard

- Complete the installation, then commission the switchboard as per the instructions in User Manual AMTNoT131-02.

© 2010 Schneider Electric - All rights reserved

Schneider Electric
35, rue Joseph Monier
CS 30323
92506 Rueil-Malmaison Cedex, France

RCS Nanterre 954 503 439
Capital social 896 313 776 €
www.schneider-electric.com

As standards, specifications and designs change from time to time, please ask for confirmation of the information given in this publication.

This document has been printed on ecological paper

Publishing: Schneider Electric
Design: Schneider Electric
Printing: